



ADDENDUM NO. 2

Date: January 16, 2024

Issued by: Sacramento City Unified School District

Project: Project #: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
Improvements

This addendum shall supersede the original Information, attachments, and specifications regarding Project No. 0510-470

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

QUESTION #8: Please confirm if the chain link posts are galvanized

RESPONSE: All posts and associated material to match the chain link fabric color.

QUESTION #9: Reference Irrigation Plan LI101A, Irrigation Legend – Where is the existing POC located?

RESPONSE: Existing POC at booster pump, top left corner of sheet.

QUESTION #10: Reference Irrigation Plan L501, Detail H – Is all sand backfill shown on this detail accurate? Including sand backfill at all irrigation lateral lines?

RESPONSE: Detail H is accurate.

QUESTION #11: Reference Irrigation Plan L501, Detail I – This detail shows a 4” perforated pipe with flex pipe on a nozzle. LI101A Irrigation legend indicates Hunter RZWS1825CV. Which is accurate?

RESPONSE: Legend is correct, Hunter RZWS.

QUESTION #12: Reference Irrigation Plan LI101A, Irrigation Legend – Lateral pipe size chart, are we supposed to figure the entire lateral line run as one size per this chart or should we figure in

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

QUESTION #14: There is some conflict between demolition and paving plan. Plan sheet CD101A calls out for existing concrete paving to be remain at the tennis court. However, plan sheet CP101 & LS16A calls out for a new concrete paving section. Please confirm if demo and new concrete paving section is needed.

RESPONSE: This concrete is to be demolished. Include in pricing to perform this similar to other demolished concrete this sheet.

QUESTION #15: May we be provided with invert elevations for the sewer line shown on sheet CU101A?

RESPONSE: We do not have this invert information. Per connection note 66, contractor is to pothole prior to trenching. Once invert is known, we can provide additional inverts as needed. Contractor should assume for bidding that this sewer line is no deeper than 5 feet.

QUESTION #16: 6.

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

QUESTION #18: Scorer's table is included in the specs but there is no call out on material plan. Please confirm its location in the plan.

RESPONSE: Scorer's table to be located behind backstop, location to be determined by District. Location not shown on plans.

QUESTION #19: Please provide specifications for Stabilized fines.

RESPONSE:

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

Sheet CS101

Added Water Supply Test.

Sheet L-56D

Note 4 Changed.

- Changed from “REFER TO SPECIFICATION SECTION 08 71 00 FOR ACCESSIBLE GATE LATCH.” to “REFER TO DETAIL E, L-56C FOR ACCESSIBLE GATE LATCH.”

Sheet L-56E

Note 4 Changed.

- Changed from “REFER TO SPECIFICATION SECTION 08 71 00 FOR ACCESSIBLE GATE LATCH.” to “REFER TO DETAIL E, L-56C FOR ACCESSIBLE GATE LATCH.”

L-56F

Detail F Callout Change

- Added “SPORTSFIELD SPECIALTIES, MODEL# GR42.” to callout.”

Sheet S-001

Structural Design Criteria C.

- Changed “ALLOWABLE PASSIVE PRESSURE” TO “ULTIMATE PASSIVE PRESSURE”

Sheet SS401

Two Notes Added.

- “TOP OF FOOTING ELEVATION (TOF = 98'-8”) IS A PLAN REFERENCE ELEVATION BASED ON A REFERENCE ELEVATION OF 100'-0” AT GRADE. SEE CIVIL DRAWINGS FOR DATUM ELEVATIONS.”
- “TOP OF FOOTING SHALL BE 1'4” BELOW FINISHED FLOOR (98'-8”), UNO.”

Sheet SS402

Note Added

One Detail Callout Changed.

- “TOP OF STEEL ELEVATION (TOS = 109'-4”) IS A PLAN REFERENCE ELEVATION BASED ON A REFERENCE ELEVATION OF 100'-0” AT GRADE. SEE CIVIL DRAWINGS FOR DATUM ELEVATIONS.”
- Detail 15A Changed from “(8) #6 VERTS, EQ SPACED” to “AT 2'-0” DIA FTG USE (6) #6 VERT BARS EQ SPACED. AT 3'-0” DIA FTG USE (9) #7 VERT BARS EQ SPACED.”

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

Sheet AS403

Detail 4 Added Note.

- “BATTING CAGES NOT PART OF DSA APPROVAL PER DSA IR A-22.”

Sheet AS404

Detail 4 Added Note.

- “BATTING CAGES NOT PART OF DSA APPROVAL PER DSA IR A-22.”

Sheet E100

Numbered Sheet Note 11.

- Added Reference to Detail 1/E400.

Sheet E200

Note Added

- “PANEL MBP1 – ATTACH TO BUILDING STUDS WITH 4X #10 WOOD SCREWS WITH WASHERS, MIN 1.5” EMBED. MAX WEIGHT 100#”

Sheet E201

Note Added

- “PANEL MBP1 – ATTACH TO BUILDING STUDS WITH 4X #10 WOOD SCREWS WITH WASHERS, MIN 1.5” EMBED. MAX WEIGHT 100#”

Sheet SB0.1

Project No: 0510-470
C.K. McClatchy High School New Softball Field and Baseball Field
ADDENDUM NO. 2

List of Attachments

- AD2.08 – C.K. McClatchy – DSA Approved Drawings (139 Pages)
- AD2.09 – C.K. McClatchy – DSA Approved Specifications (772 Pages)
- AD2.10 – C.K. McClatchy – Revised Sheet CP101, Joint Layout Sketch (1 Page)
- AD2.11 – C.K. McClatchy – Miscellaneous Detail Clarifications (5 Pages)
- AD2.12 – C.K. McClatchy – Scoring Table & Stabilized Fines Clarification (3 Pages)
- AD2.13 – C.K. McClatchy – Revised Specification Section 32 15 40 (5 Pages)

END OF ADDENDUM NO. 2

Acknowledgement of this Addendum will be required at time of bid.