PROJECT MANUAL AND SPECIFICATIONS FOR

DIVISION SECTION TITLE

SACRAMENTO CITY UNIFIED SCHOOL DISTRICT REVISED FEBRUARY 06, 2023

- Allowance Expenditure Directive Form 00 63 40
- 00 63 47
- Daily Force Account Report Proposed Change Order Form 00 63 57
- Change Order Form 00 63 63

SECTION 01 57 13

SECTION 02 41 00

SITE DEMOLITION

PART 1 – GENERAL

1.01 SUMMARY

- A. RELATED SECTIONS
 - 1. The General Conditions, Supplementary Conditions and Division 1 are fully applicable to this Section, as if repeated herein.
 - 2. Section 01 50 00 Construction Facilities and Temporary Controls.
 - 3. Section 01 50 13 Construction Waste Management and Disposal.
 - 4. Section 31 00 00 Earthwork.
 - 5. Section 31 13 16 Tree Protection.

1.02 REGULATORY REQUIREMENTS

- A. Conform to applicable jurisdictional authority regulations and codes for disposal of debris.
- B. Coordinate clearing Work with utility companies
- C. Maintain emergency access ways at all times.
- D. Contractor shall comply with all applicable laws and ordinances regarding hazardous materials,

1.05 **PROTECTION**

- A. Adequate protection measures shall be provided to protect workmen and passers-by on and off the site. Adjacent property shall be fully protected throughout the operations. Blasting will not be permitted. Prevent damage to adjoining improvements and properties both above and below grade. Restore such improvements to original condition should damage occur. Replace trees and shrubs outside building area disturbed by operations.
- B. In accordance with generally accepted construction practices, the Contractor shall be solely and completely responsible for working conditions at the job site, including safety of all persons and property during performance of the work. This requirement shall apply continuously and shall not be limited to normal working hours.
- C. Safety Precautions Prevent damage to existing elements identified to remain or to be salvaged, and prevent injury to the public and workmen engaged on site. Demolish roofs, walls and other building elements in such manner that demolished materials fall within foundation lines of building. Do not allow demolition debris to accumulate on site. Pull down hazardous work at end of each day; do not leave standing or hanging overnight, or over weekends.
 - 1. Protect existing items which are not indicated to be altered. Protect utilities designated to remain from damage.
 - 2. Protect trees, plant growth, and features designated to remain as final landscaping as shown on drawings.
 - 3. Protect benchmarks from damage or displacement.
- D. Trees: Carefully protect existing trees that are to remain. Provide temporary irrigation as necessary to maintain health of trees.
- E. Fire Safety: The contractor shall conform to chapter 33 of the California Fire Code (CFC), "Fire Safety During Construction and Demolition", at all times during the construction process. A copy of this chapter can be provided.
- F. Any construction review of the Contractor's performance conducted by the Geotechnical Engineer is not intended to include review of the adequacy of the Contractor's safety measures, in, on, or near the construction site.
- G. Surface Drainage: Provide for surface drainage during period of construction in manner to avoid creating nuisance to adjacent areas. The contractor shall make a reasonable effort on a daily basis to keep all excavations and the site free from water during entire progress of work, regardless of cause, source, or nature of water.
- H. Adjacent streets and sidewalks shall be kept free of mud, dirt or similar nuisances resulting from earthwork operations.
- I. The site and adjacent influenced areas shall be watered as required to suppress dust nuisance. Dust control measures shall be in accordance with the local jurisdiction.

SITE DEMOLITION 02 41 00 - 3 E. Coordinate the time and duration of all system disconnects with Owner.

3.03 DEMOLITION

- A. General Requirements
 - 1. Clear areas required for access to site and execution of Work, including pavements, structures, foundations, vegetation, trash and debris.
 - 2. Coordinate with Owner the time of day and route to remove demolished materials from premises.
 - 3. Remove demolished materials from site as work progresses. Upon completion of work, leave areas of work in clean condition.
 - 4. Remove all buried debris, rubble, trash, or other material not deemed suitable by the Geotechnical Engineer.
 - 5. Fill all voids or excavations resulting from clearing, demolition, or removal of vegetation with specified fill material.
- B. Fixture and Equipment Removal:
 - 1. Remove existing fixtures and equipment as identified and shown on drawings and required by Architect.
 - 2. Verify all service connections to fixtures and equipment designated for removal have been properly disconnected.
 - 3. Remove all conductors from conduit at all abandoned circuits.
- 3.04 UTILITY AND BUILDING SERVICES REMOVAL AND RE-INSTALLATION
 - A. Where crossing paths and potential points of interference with existing utility services are shown or can be reasonably inferred from surface conditions or evidence of subsurface systems, such as meter boxes, vaults, relief vents, cleanouts and similar components.
 - 1. Review all contract documents showing crossing paths and potential points of interference.
 - 2. Pothole or determine by other means the accurate depth and location of such utilities.
 - Incorporate all costs required to complete work under this contract, including additional trenching, re-routing of existing and new utilities, and all means necessary to construct work under this contract.
 - 4. No additional cost to the Owner will be allowed for work necessary to accommodate utility conflicts where such crossing paths are shown on contract drawings or can be reasonably inferred from surface conditions or components.
 - B. Remove all conductors from conduit at all abandoned electrical circuits.

C. (der) 1.03.960139e Td [040.)-1.00675(aban)-1.00142(do)-0.982777(ne) 1.03871e re[4.)-8(wci58807(such an4c0142

- 8. Selected equipment of such sizes and capacities that the existing environment is disturbed as little as possible, and to afford ease of mobility within limited and relatively confined work areas. Make every effort to preserve the topography in its natural state.
- 9. Keep drains, catch basins, surface drainage courses and related drainage system components clear of debris and construction materials.
- 10. Remove irrigation piping and appurtenances as necessary within area of work, unless noted otherwise to remain. Replace irrigation piping and appurtenances to irrigate new and/or existing landscaping. Contractor shall be responsible for temporary landscape irrigation until such time that irrigation system is restored and operational.
- 3.07 DISPOSAL

DOOR HARDWARE 08 71 00 - 1

- 1. NFPA 80 Standard for Fire Doors and Other Opening Protectives
- 2. NFPA 105 Standard for Smoke Door Assemblies and Other Opening Protectives
- F. UL Underwriters Laboratories.
 - 1. UL 10C Standard for Positive Pressure Fire Tests of Door Assemblies
 - 2. UL 305 Standard for Panic Hardware
- G. WHI Warnock Hersey Incorporated
- H. SDI Steel Door Institute

1.03 SUBMITTALS & SUBSTITUTIONS

- A. General: Submit in accordance with Conditions of the Contract and Division 1 Specification sections.
- B. Submit product data (catalog cuts) including manufacturers' technical product information for each item of door hardware, installation instructions, maintenance of operating parts and finish, and other information necessary to show compliance with requirements.
- C. Submit six (6) copies of schedule organized vertically into "Hardware Sets" with index of doors and headings, indicating complete designations of every item required for each door or opening. Include following information:
 - 1. Include a Cover Sheet with;
 - a. Job Name, location, telephone number.
 - b. Architects name, location and telephone number.
 - c. Contractor's name, location, telephone number and job number.
 - d. Suppliers name, location, telephone number and job number.
 - e. Hardware consultant's name, location and telephone number.
 - 2. Job Index information included;
 - a. Numerical door number index including; door number, hardware heading number and page number.
 - b. Complete keying information (referred to DHI hand-book "Keying Systems and Nomenclature"). Provision should be made in the schedule to provide keying information when available; if it is not available at the time the preliminary schedule is submitted.
 - c. Manufacturers' names and abbreviations for all materials.
 - d. Explanation of abbreviations, symbols, and codes used in the schedule.
 - e. Mounting locations for hardware.
 - f. Clarification statements or questions.
 - g. Catalog cuts and manufacturer's technical data and instructions.
 - 3. Vertical schedule format sample:
 - a. Single or pair with opening number and location.
 - b. Degree of opening

- c. Hand of door(s)
- d. Door and frame dimensions and door thickness.
- e. Label requirements if any.
- f. Door by frame material.
- g. (Optional) Hardware item line #.
- h. Keyset Symbol.
- i. Quantity.
- j. Product description.
- k. Product Number.
- I. Fastenings and other pertinent information.
- m. Hardware finish codes per ANSI A156.18.
- n. Manufacture abbreviation.
- D. Make substitution requests in accordance with Division 1. Substitution requests must be made prior

DOOR HARDWARE 08 71 00 - 4

- C. Provide locked storage area for hardware, protect from moisture, sunlight, paint, chemicals, etc.
- D. Contractor to inventory door hardware jointly with representatives of hardware supplier and hardware installer until each all are satisfied that count is correct.

1.06 WARRANTY

- A. Provide warranties of respective manufacturers' regular terms of sale from day of final acceptance as follows:
 - 1. Locksets: "L" Series (3) years "ND" Ten (10) years.
 - 2. Electronic: One (1) year.
 - 3. Closers: Thirty (30) years –1260 twenty (20) years –Concealed High Security fifteen (15) years except electronic closers shall be two (2) years.
 - 4. Exit devices: Three (3) years.
 - 5. All other hardware: Two (2) years.

1.07 MAINTENANCE

A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

Item	Manufacturer	Acceptable Substitutes	
Hinges	lves	Hager, Stanley, McKinney	
Locks, Latches			

SACRAMENTO CITY UNIFIED SCHOOL DISTRICT VERSION DATE JANUARY 6, 2023

- 10. Provide cylindrical locksets exceeding the ANSI/BHMA A156.2 Grade 1 performance standards for strength, security, and durability in the categories below:
 - a. Abusive Locked Lever Torque Test minimum 3,100 inch-pounds without gaining access
 - b. Offset lever pull minimum 1,600-foot pounds without gaining access
 - c. Vertical lever impact minimum 100 impacts without gaining access
- 11. Cycle life tested to minimum 16 million cycles per ANSI/BHMA A156.2 Cycle Test with no visible lever sag or use of performance aids such as set screws or spacers
- 12. Cylinders: Refer to "KEYING" article, herein.
- 13. Provide solid steel anti-rotation through bolts and posts to control excessive rotation of lever.
- 14. Provide lockset that allows lock function to be changed to over twenty other common functions by swapping easily accessible parts.
- 15. Provide locksets with separate anti-rotation thru-bolts, and no exposed screws.
- 16. Provide independently operating levers with two external return spring cassettes mounted under roses to prevent lever sag.
- 17. Provide standard ASA strikes unless extended lip strikes are necessary to protect trim.

- 1. Thresholds shall not exceed 1/2" in height, with a beveled surface of 1:2 maximum slope.
- 2. Set thresholds in a full bed of butyl-rubber or polyisobutylene mastic sealant complying with requirements in Division 7 "Thermal and Moisture Protection".
- 3. Use ¼" fasteners, red-head flat-head sleeve anchors (SS/FHSL).
- 4. Thresholds shall comply with CBC Section 11B-404.2.5.
- K. Seals and Surface Applied Hardware: Zero as scheduled.

1. 2.	Smoke Seal:488S-BK Weather Seal: 488S-BK	Black 628 finish
-and-		
	8780N	Factory
3.	Door Sweep: 328AA	689 finish
4	139SS (Wood doors) (Use only where required by fire code)	630
	a. Astragal by door manufacturer at HM door	
5.	Drip Guard: 17D x 4" PDW (Exterior doors exposed to rain)	628

- 6. Door Bottom: Use automatic door bottoms only if required by code.
- 7. Provide silicone gasket at all rated and exterior doors.
- 8. Fire-rated Doors, Resilient Seals: UL10C Classified complies with NFPA 80 & NFPA 252. Coordinate with selected door manufacturers' and selected frame manufacturers' requirements.
- 9. Fire-rated Doors, Intumescent Seals: Furnished by selected door manufacturer. Furnish firelabeled opening assembly complete and in full compliance with UL10C Classified complies with NFPA 80 & NFPA 252. Where required, intumescent seals vary in requirement by door type and door manufacture -- careful coordination required.
- 10. Smoke & Draft Control Doors, Provide UL10C Classified complies with NFPA 80 & NFPA 252 for use on "S" labeled Positive Pressure door assemblies.
- L. Door Shoes & Door Top Caps: Provide door shoes at all exterior wood doors and top caps at all exterior out-swing doors.
- M. Silencers: Ives as scheduled.
 - 1. 654A, 655A, 623A
 - 2. Furnish silencers for interior hollow metal frames, 3 for single doors, 2 for pairs of doors. Omit where sound or light seals occurs, or for fire-resistive-rated door assemblies.
- N. Keying: Schlage as scheduled.
 - 1. Furnish a Proprietary Schlage master key system as directed by the owner or architect. Key system to be designated and combination-d by the Schlage Master Key Department even if pinned by the Authorized Key Center, Authorized Security Center or a local authorized

Black

- 2. A detailed keying schedule is to be prepared by the owner and/or architect in consultation with a representative of Allegion or an Authorized Key Center or Authorized Security Center. Each keyed cylinder on every keyed lock is to be listed separately showing the door #, key group (in BHMA terminology), cylinder type, finish and location on the door.
- 3. Establish a new master key system for this project as directed by the keying schedule.
- 4. Furnish all cylinders in the Schlage conventional style except the exit device and removable mullion cylinders which will be supplied in Schlage Full Size Interchangeable Core (FSIC). Pack change keys independently (PKI).
- 5. Furnish PrimusXP "Classic" keyway Patent Protected Schlage cylinders where noted. Furnish all other cylinders in matching conventional "Classic" keyway. Furnish Patent Protected Schlage keys for all cylinders. (e.g., Primus XP Classic Keyway for patent protected / Maximum control) (with mix of conventional "Classic" keyway)
- 6. Furnish construction keying for doors requiring locking during construction.
 - a. For FSIC systems provide 23-030-ICX Full Size Construction Cores
 - b. For FSIC systems provide ten 48-101-ICX Construction Keys
 - c. For FSIC systems provide two 48-056-ICX Control Keys (const.)
 - For FSIC systems provide two control keys for installing the permanent cores (49- 056 for "Classic" keyways, 48-052-XP for "Classic Primus") (49-003 for "Everest Conventional", 48-005–XP for "Everest Primus")

-OR-

- 7. Furnish construction keying for doors requiring locking during construction.
 - a. For "Split Key" Construction Cylinders (non-IC cylinders) specify "CK" for each keyed cylinder.
 - b. Provide ten Construction Keys (48-104 "Classic", 48-008 "Everest")
 - c. Provide two Extractor Tools (35-057)
- 8. Furnish all keys with visual key control.
 - a. Stamp key "Do Not Duplicate".
- 9. Furnish mechanical keys as follows:
 - a. Furnish 2 cut change keys for each different change key code.
 - b. Furnish 1 uncut key blank for each change key code.
 - c. Furnish 6 cut maste7-hr–0.97212)

DOOR HARDWARE 08 71 00 - 12 Authority Having Jurisdiction (AHJ). The inspection of the swinging fire doors shall be performed by a certified FDAI (Fire Door Assembly Inspector) with knowledge and understanding of the operating components of the type of door being subjected to the inspection. The record shall list each fire door assembly throughout the project and include each door number, an itemized list of hardware set components at each door opening, and each door location in the facility.

3.02 INSTALLATION

- A. Install hardware in accordance with manufacturer's instructions and requirements of DHI.
- B. Use the templates provided by hardware item manufacturer.
- C. Mounting heights for hardware shall be as recommended by the Door and Hardware Institute. Operating hardware will to be located between 34" and 44" AFF.
- D. Set units level, plumb and true to line and location. Adjust and reinforce the attachment substrate as necessary for proper installation and operation.
- E. Drill and countersink units that are not factory-prepared for anchorage fasteners. Space fasteners and anchors in accordance with industry standards.
- F. Set thresholds for exterior doors in full bed of butyl-rubber sealant.
- G. If hand of door is changed during construction, make necessary changes in hardware at no additional cost.

bs nhtardavae87()}7111@47(talle):0.01t207teovaittacsec()=0e97892(005(e)11a77(7)@(p)0)11.028030(4)1e57kHeat()-0.97212conno

DOOR HARDWARE

C. The Door Schedule on the Drawings indicates which hardware set is used with each door.

Manufacturers Abbreviations (Mfr.)

GLY	=	Glynn-Johnson Corporation	Overhead Door Stops
IVE	=	lves	Hinges, Pivots, Bolts, Coordinators, Dust Proof Strikes,
			Push Pull & Kick Plates, Door Stops & Silencers

EA	ELEC EXIT DEVICE	AD-300-993R-70-MT-RHO-L-LRX 12/24 626		SCE
	TRIM VDC (PROVIDE	ED BY DIVISION 28)		

_ _ -
SECTION 260529

ELECTRICAL HANGERS AND SUPPORTS

PART 1 - GENERAL

1.01 SUMMARY

- A. Work included: Labor, materials, and equipment necessary to complete the installation required for the item specified under this Division, including but not limited to:
 - 1. Conduit supports.
 - 2. Equipment supports.
 - 3. Fastening hardware.
- B. Related Work: Consult all other Sections, determine the extent and character of related Work, and properly coordinate Work specified herein with that specified elsewhere to produce a complete installation.
 - 1. The General Conditions, Supplementary Conditions and Division 1 are fully applicable to this Section, as if repeated herein.
 - 2. Division 03: Cast-in-place concrete. Concrete equipment pads.
 - 3. Division 05: Miscellaneous metals. Hangers for electrical equipment.
 - 4. Division 09: Ceiling suspension systems. Slack support wires.

1.02 REFERENCES

- A. Comply with the latest edition of the following applicable Specifications and standards except as otherwise indicated or specified:
 - 1. Underwriters Laboratories, Inc. (UL):

UL 2239; Hardware for the Supports of Conduit, Tubing and Cable.

1.03 SYSTEM DESCRIPTION

- A. Provide devices specified in this Section and related Sections for support of electrical equipment furnished and installed under Division 26.
- B. Provide support systems that are adequate for the weight of equipment, conduit and wiring to be supported.

1.04 SUBMITTALS

- A. Submit in accordance with the requirements of Section 260010: Basic Electrical Requirements, the following items:
 - 1. Data/catalog cuts for each product and component specified herein.
 - 2. Clearly mark on each data sheet the specific item(s) being submitted and the proposed application.
 - 3. Submit Manufacturer's installation instructions.
- 1.05 QUALITY ASSURANCE

SACRAMENTO CITY UNIFIED SCHOOL DISTRICT REVISED SEPTEMBER 30, 2022

- A. One-hole strap, steel, or malleable iron, with malleable iron clamp-back spacer for surface mounted wall and ceiling applications.
 - 1. Use malleable strap with spacers for exterior and wet locations.
 - 2. Use steel strap without spacers for interior locations.
- B. Steel channel conduit strap for support from construction channel.
- C. Steel conduit hanger for pendant support with threaded rod
- D. Steel wire conduit support strap for support from independent #12-gauge hanger wires.

PART 3 - EXECUTION

3.01 EXAMINATION

A. Contractor shall thoroughly examine Project site conditions for acceptance of supporting device installation to verify conformance with Manufacturer and Specification tolerances. Do not commence with installation until all conditions are made satisfactory.

3.02 PREPARATION

- A. Coordinate size, shape, and location of concrete pads with Division 03, Cast-in-place concrete.
- B. Layout support devices to maintain headroom, neat mechanical appearance and to support the equipment loads.
- C. Where indicated on the Contract Documents, install freestanding electrical equipment on concrete pads.

3.03 INSTALLATION

- A. Furnish and install supporting devices as noted throughout Division 26.
- B. Electrical device and conduit supports shall be independent of all other system supports that are not structural elements of the building, unless otherwise noted.
- C. Fasten hanger rods, conduit clamps, outlet, and junction boxes to building structure using precast inserts, expansion anchors, preset inserts, or beam clamps.
- D. Use toggle bolts or hollow wall fasteners in hollow masonry, plaster or gypsum board partitions and walls.
- E. Use expansion anchors or preset inserts in solid masonry walls.
- F. Use self-drilling anchors, expansion anchor or preset inserts on concrete surfaces.
- G. Use sheet metal screws in sheet metal studs and wood screws in wood construction.
- H. Do not fasten supports to piping, ductwork, mechanical equipment, conduit, or acoustical ceiling suspension wires.
- I. Do not drill structural steel members unless first approved in writing by the Architect or Structural Engineer.
- J. Fabricate supports from structural steel or steel channel, rigidly welded, or bolted to present a neat appearance. Use hexagon head bolts with spring lock washers under all nuts.

SECTION 260531

CONDUIT

PART 1 - GENERAL

1.01 SUMMARY

- A. Work included: Labor, materials, and equipment necessary to complete the installation required for the item specified under this Division, including but not limited to:
 - 1. Rigid steel conduit and fittings.
 - 2. PVC insulated rigid steel conduit and fittings.
 - 3. Intermediate metal conduit and fittings.
 - 4. Electrical metallic tubing and fittings.
 - 5. Flexible metallic conduit and fittings.
 - 6. Liquidtight flexible metallic conduit and fittings.
 - 7. Miscellaneous conduit fittings and products.
- B. Related Work: Consult all other Sections, determine the extent and character of related Work, and properly coordinate Work specified herein with that specified elsewhere to produce a complete installation.
 - 1. The General Conditions, Supplementary Conditions and Division 1 are fully applicable to this Section, as if repeated herein.
 - 2. Division 01: Cutting and patching.
 - 3. Division 07: Sheet metal flashing and trim.
 - 4. Division 09: Painting. Exposed conduit and other devices.

1.02 REFERENCES

- A. Comply with the latest edition of the following applicable Specifications and standards except as otherwise indicated or specified:
 - 1. American National Standards Institute, Inc. (ANSI):

ANSI C80.1;	Rigid Steel Conduit, Zinc-Coated.
ANSI C80.3;	Electrical Metallic Tubing, Zinc Coated.

- UL 514B; Conduit, Tubing and Cable Fittings.
- UL 635; Insulating Bushings.
- UL 797; Electrical Metallic Tubing Steel.
- UL 1242; Intermediate Metal Conduit Steel.
- National Electrical Manufacturer Association (NEMA): NEMA RN1; PVC Externally coated Galvanized Rigid Steel Conduit.
- 1.03 SUBMITTALS
 - A. Submit in accordance with the requirements of Section 260010: Basic Electrical Requirements the following items:

- c. Thomas & Betts Corp.
- d. Spring City Electrical Manufacturing Co.
- B. Substitutions: Under provisions of Section 260010: Basic Electrical Requirements.

2.02 GALVANIZED RIGID STEEL CONDUIT (GRS)

- A. Conduit: Full weight, threaded, hot-dip galvanized steel, conforming to ANSI C80.1 and UL
 6.
- B. Standard threaded couplings, locknuts, bushings, and elbows: Only materials of steel or malleable iron are acceptable. Locknuts shall be bonding type with sharp edges for digging into the metal wall of an enclosure; provide two locknuts at each box or can, inside and outside.
- C. Three-piece couplings: Hot dip galvanized, cast malleable iron.
- D. Insulating bushings: Threaded polypropylene or thermosetting phenolic rated 150-degree C minimum.
- E. Insulated grounding bushings: Threaded cast malleable iron body with insulated throat and steel "lay-in" ground lug with compression screw.
- F. Insulated metallic bushings: Threaded cast malleable iron body with plastic insulated throat rated 150-degrees C.
- G. All fittings and connectors shall be threaded.
- 2.03 PVC INSULATED GALVANIZED RIGID STEEL CONDUIT (PVC GRS)
 - A. Conduit: Full weight, threaded, hot-dip galvanized steel, conforming to ANSI C80.1 and NEMA RN-1 with nominal 20 or 40 mil thermoplastic vinyl coating, heat fused and bonded to the exterior of the conduit.
 - B. Fittings: Conduit couplings and connectors shall be as specified for galvanized rigid steel conduit and shall be factory PVC coated with an insulating jacket equivalent to that of the coated material.

2.04 INTERMEDIATE METAL CONDUIT (IMC)

- A. Conduit: Hot dip galvanized steel meeting the requirements of CEC Article 345 and conforming to ANSI C80.6 and UL 1242.
- B. Fittings: Conduit couplings, connector and bushing shall be as specified for galvanized rigid steel conduit. Integral retractable type IMC couplings are also acceptable.
- 2.05 ELECTRICAL METALLIC TUBING (EMT)
 - A. Conduit: Shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam and hot dip galvanized after fabrication. Conduit shall conform to ANSI C80.3 Specifications and shall meet UL requirements.
 - B. Set screw type couplings: Hot dip galvanized, steel, UL listed concrete tight. Use set screw type couplings with four setscrews each of conduit sizes over 2 inches. Setscrews shall be of case-hardened steel with hex-head and cup point to firmly seat in wall of conduit for positive grounding.

- C. Intermediate metal conduit (IMC): Can be used for the same application as galvanized rigid steel conduit as specified herein, except for hazardous locations prohibited by CEC or Local Codes.
- D. Electrical metallic tubing (EMT): Can be used exposed or concealed for interior electrical feeders 4" and smaller, interior power and lighting branch circuits and low tension distribution system where run above suspended ceilings, in concrete slabs and walls not in contact with earth; in stud walls, furred spaces and crawl spaces. EMT shall not be installed exposed below 8 feet above the finish floor except within electrical, communication or signal rooms or closets (subject to physical damage).
- E. Flexible metallic conduit (FMC): Can be used only in dry locations for connections from an adjacent outlet box or conduit to all motors, transformers, vibrating equipment or machinery, controllers, solenoid valves, float and flow switches or similar devices and to luminaires installed in suspended ceilings.
- F. Liquidtight flexible metallic conduit (LFMC): Can be used in wet or damp locations for connections from adjacent outlet box or conduit to all motors, transformers, vibrating equipment or machinery, controllers, solenoid valves, float and flow switches or similar devices. These areas are typically food preparation and dishwashing areas, sump wells, loading docks, pump rooms, exterior areas, etc.
- G. Fire-Resistive Systems: Refer to CEC Article 728. All devices utilized, mountings, and supports shall be listed as part of the fire-resistive system.

3.03 PREPARATION

A. Locations of conduit runs shall be planned in advance of the installation and coordinated with ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor

concrete slabs or wall and shall not be placed between reinforcing steel and the bottom of floor slabs.

terminations are subject to vibration, use bonding bushings or wedges to assure electrical continuity. Where subject to vibration or dampness, use insulating bushings to protect conductors. Install grounding bushings or bonding jumpers on all conduits terminating at concentric or eccentric knockouts.

- D. Conduit terminations exposed at weatherproof enclosures and cast outlet boxes shall be made watertight using specified connectors and hubs.
- E. Stub-up connections: Extend conduits through concrete floor for connection to freestanding equipment with an adjustable top or coupling threaded inside for plugs and set flush with the finished floor. Extend conductors to equipment with rigid steel conduit; flexible metal conduit may be used 6 inches above the floor. Where equipment connections are not made under this contract, install screwdriver operated threaded flush plugs with floor.
- F. Install specified cable sealing bushings on all conduits originating outside the building walls and terminating in switchgear, cabinets, or gutters inside the building. Install cable sealing bushings or raceway seal for conduit terminations in all grade level or below grade exterior pull, junction, or outlet boxes.
- G. Raceway seal: Inject into wire filled raceways, a pre-formulated rigid 2 lbs. density polyurethane foam which expands a minimum 35 times its original bulk. F cm BT /R14578 Td [G.Cn17(e)1.0

3.08 HAZARDOUS LOCATIONS

- A. Use rigid steel conduit only.
- B. Install UL approved sealing fittings that prevent passage of explosive vapors in accordance with the Manufacturers written instructions. Locate fittings at suitable, approved, accessible locations and fill them with UL-listed sealing compound. For concealed raceways,

CONDUIT 26 05 31 - 2

END OF SECTION

BOXES 26 05 33 - 1

SECTION 26 05 33

BOXES

PART 1 - GENERAL

1.01 SUMMARY

BOXES 26 05 33 - 2

- E. Locate outlet boxes above hung ceilings having concealed suspension systems, adjacent to openings for removable recessed luminaires.
- F. Do not install outlet boxes back-to-back, separate boxes by at least 6". In fire-rated walls separate boxes by at least 24" and wall stud.

BOXES 26 05 33 - 5

SECTION 26 05 43

UNDERGROUND DUCTS AND STRUCTURES

PART 1 - GENERAL

1.01 SUMMARY

- A. Work included: Labor, materials, and equipment necessary to complete the installation required for the item specified under this Division, including but not limited to:
 - 1. Underground conduits and ducts.
 - 2. Handhole and pullboxes.
 - 3. Excavation, trenching and backfill.
- B. Related Work: Consult all other Sections, determine the extent and character of related Work, and properly coordinate Work specified herein with that specified elsewhere to produce a complete installation.
 - 1. The General Conditions, Supplementary Conditions and Division 1 are fully applicable to this Section, as if repeated herein.
 - 2. Division 31 Earthwork: General requirements for Excavation and Backfill and related items for ducts, manholes, pullboxes and handholes.
 - 3. Division 03 Cast-in-place concrete: Protective envelope for ducts.

1.02 REFERENCES

- A. Comply with the latest edition of the following applicable Specifications and standards except as otherwise indicated or specified:
 - 1. American Concrete Institute (ACI):

ACI 318; Building Code Requirements for Structural Concrete

- 2. American National Standards Institute, Inc. (ANSI):
- 3. American Society for Testing And Materials (ASTM):

UNDERGROUND DUCTS AND STRUCTURES 26 05 43 - 2

- 3. Shop Drawings showing details and design calculations for precast handholes, including reinforced steel.
- 4. Submit Manufacturer's installation instructions.
- 5. Complete bill of material listing all components.

1.05 QUALITY ASSURANCE

- A. All materials, equipment and parts comprising the units specified herein shall be new, unused, and currently under production.
- B. Only products and applications listed in this Section may be used on the Project unless otherwise submitted and approved.
- C. Precast concrete vaults shall be designed and fabricated by an experienced and acceptable precast concrete manufacturer. The manufacturer shall have been regularly and continuously engaged in the manufacture of precast concrete units similar to that indicated in the project specifications or drawings for at least 10 years.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

- A. Products furnished by the following Manufacturers shall be acceptable if in compliance with all features specified herein and indicated on the Drawings.
 - 1. Underground precast concrete utility structures:
 - a. Oldcastle Enclosure Solutions.
 - b. Jensen Precast.
 - 2. Conduits, ducts and fittings:
 - a. Prime Conduit.
 - b. JM Eagle.
 - c. Cantex.
UNDERGROUND DUCTS AND STRUCTURES 26 05 43 - 6

ACCESS CONTROL SYSTEM 28 10 00 - 1

- 6. Access control hardware shall continue to fully function in the event of communication loss to the central server.
- 7. Power to control panels shall be hardwired in conduit.
- 8. All door controllers shall have battery backup.

1.03 RELATED REQUIREMENTS

- A. Division 01 General Requirements
- B. Section 08 71 00 Door Hardware
- C. Section 27 00 00 Communications
- D. Section 27 05 00 Common Work Results for Communication Systems.
- E. Section 27 10 00 Structured Cabling
- F. Americans with Disability Act (ADA)

1.04 REFERENCES

- A. See section 27 00 00 for requirements.
- 1.05 **DEFINITIONS**
 - A. See section 27 00 00 for requirements.

1.06 SYSTEM REQUIREMENTS

- A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing Access Control systems and integrate into the Districts Avigilon ACM Enterprise installation.
- 1.07 SUBMITTALS
 - A. See section 27 00 00 for requirements.
- 1.08 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS
 - A. See section 27 00 00 for requirements.

B. Shop drawings are required for this section.

PART 2 - PRODUCTS

2.01 GENERAL

- A. Manufacturers See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. Contractor shall provide all components needed for complete and satisfactory installation and operation.
- D. Product Availability
 - 1. Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
 - 2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. See Appendix A at the end of this document for pre-approved materials.
- B. Substitutions require proof of equivalence and prior approval by District and/or it's

2.03 EXTRA STOCK

- A. For each increment of 100 controlled doors furnish:
 - 1. Quantity 5 of current model door controller.
 - 2. Quantity 7 of current model card reader.

PART 3 - EXECUTION

3.01 ACCEPTABLE INSTALLERS

- A. The equipment shall only be installed by Contractors who are qualified to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing electronic access control equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to bidding the job. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

2. Surface raceway and components shall be Wiremold 2300.

3.05 EQUIPMENT INSTALLATION

3.09 CONFIGURATION

- A. Program all network equipment with network IP address information obtained from Electronics/Lock Shop.
- B. All equipment to be fully configured and tested for functionality prior to testing.

3.10 FIELD QUALITY CONTROL AND TESTING

- A. Upon reaching substantial completion, perform a complete test and inspection of the system. If found to be installed and operating properly, notify District of your readiness to perform the formal Test & Inspection of the complete system.
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.
- C. During the formal Test & Inspection (Commissioning) of the system the Contractor shall have personnel available with tools and equipment to inspect wiring, devices, and system operation.

DESCRIPTION	MFG	PART NUMBER
Door Controller (1-door)	Avigilon	AC-MER-CONT-LP1501
Door Controller (2-door)	Avigilon	AC-MER-CONT-LP1502
Door Controller (1- door/slave PoE)	Avigilon	AC-MER-CON-MR51E
2-Reader Interface Module	Avigilon	AC-MER-CON-MR52
Card Reader	Avigilon	AC-ING-READ-APTIQ-SNG-MT15
Power Supply/Cabinet (2 Door)	Avigilon	AC-LSP-2DR-MER-LCK
Power Supply/Cabinet (8 Door)	Avigilon	AC-LSP-8DR-MER-LCK
Electronic Surface Strike (rim style)	Assa Abloy/HES	9600
Electronic Surface Strike (rim style)	Von Duprin	6300
Electronic Latch Set (mortise)	Schlage	ND96EUPD
Latch Retraction Motor (Von Duprin)	Von Duprin	QEL
Latch Retraction Motor (Jackson)	Command Access	MLRK1-JAC12REX

VIDEO SURVEILLANCE 28 20 00 - 1

1.03 RELATED REQUIREMENTS

- A. Division 01 General Requirements
- B. Section 27 00 00 Communications
- C. Section 27 05 00 Common Work Results for Communication Systems.
- C. Section 27 10 00 Structured Cabling

1.04 QUALIFICATIONS

- A. Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five years' experience installing Video Surveillance equipment systems.

1.05 SYSTEM REQUIREMENTS

A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing Video Surveillance system.

1.06 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

- A. See section 27 00 00 for requirements.
- B. Shop drawings are required for this section

1.07 SUBMITTALS

A. See section 27 00 00 for requirements.

1.08 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.09 CLOSEOUT DOCUMENTS

A. See section 27 00 00 for requirements.

PART 2 - PRODUCTS

2.01 GENERAL

- A. See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. Contractor shall provide all components needed for complete and satisfactory installation/operation.
- D. Product Availability
 - 1. Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
 - 2. Subject to compliance with these specifications, products and systems included in this

- C. Comply with highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.

3.06 PATHWAY AND EQUIPMENT INSTALLATION

- A. Install all conduit and pathway per design documents. Refer to 27 05 00 for additional information/requirements.
- B. Install all Cat6A cables per design documents. Refer to Section 27 10 00 for additional information/requirements.
- B. Equipment to be installed per manufacturer's instructions.
- C. Devices requiring PoE power shall be connected to a PoE switch in the MDF/IDF data rack verify for adequate PoE power capacity.

3.07 CONFIGURATION

- A. Program cameras and/or NVR with network IP address using the following scheme. Note: x=site octet, contact District Electronics shop for site information.
 1. Compress 10 x 252 101
 - 1. Cameras: 10.x.253.101 = Camera 1, 10.x.253.102 = Camera 2...
 - 2. NVR: 10.x.253.1
 - 3. POE Switch: 10.x.253.10 = 1st switch, 10.x.253.11 = 2nd switch...
 - 4. Gateway: 10.x.0.1
 - 5. Subnet Mask: 255.255.0.0
- B. All equipment to be fully configured and tested for functionality prior to District acceptance testing.

3.08 CAMERA VIEW

A. Adjust view aim, zoom and focus camera to show intended view from design documents.

3.09 FIELD QUALITY CONTROL AND TESTING

- A. Upon completion of network programming and initial view setting, notify District of your readiness to perform the formal camera view review with District or its representative. Make all adjustments required from District review.
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.

VIDEO SURVEILLANCE

Network Video Recorder 48TB

SECTION 31 00 00

EARTHWORK

PART 1 - GENERAL

1.01 SUMMARY

- A. RELATED SECTIONS
 - 1. The General Conditions, Supplementary Conditions and Division 1 are fully applicable to this Section, as if repeated herein.
 - 2. Section 01 50 00, Construction Facilities and Temporary Controls.
 - 3. Section 01 57 13, Erosion Control
 - 4. Section 31 23 33, Trenching and Backfilling.
 - 5. Section 32 12 00, Asphalt Concrete Paving.
 - 6. Section 32 16 00, Site Concrete.

1.02 SUBMITTALS

- A. Refer to Section 01 33 00.
- B. Manufacturer's Data: Submit list and complete descriptive data of all products proposed for use. Include manufacturer's specifications, published warranty or guarantee, installation instructions, and maintenance instructions.

1.03 QUALITY ASSURANCE

- A. Use only new materials and products, unless existing materials or products are specifically shown otherwise on the Drawings to be salvaged and re-used.
- B. All materials, components, assemblies, workmanship and installation are to be observed by the Owner's Inspector of Record. Work not so inspected is subject to uncovering and replacement.
- C. The representatives of the Owner's testing lab will not act as supervisor of construction, nor will they direct construction operations. Neither the presence of the Owner's testing lab representatives nor the testing by the Owner's testing lab shall excuse the contractors or subcontractors for defects discovered in their work during or following completion of the project. Correcting of inadequate compaction or moisture content is the sole responsibility of the contractor.
- D. Tests (See Part 3 for Compaction Testing).
- E. Contractor shall be solely responsible for all subgrades built. Failures resulting from inadequate

compaction or moisture content are the responsibility of the contractor. Contractor shall be solely responsible for any and all repairs.

- 1.04 WARRANTY
 - A. Refer to General Conditions and Section 01 78 36.

this Section and that arrangements have been made to properly store, handle and protect such materials and work.

1.07 PROJECT CONDITIONS

- A. Existing civil, mechanical and electrical improvements are shown on respective site plans to the extent known. Should the Contractor encounter any deviation between actual conditions and those shown, he is to immediately notify the Architect before continuing work.
- B. Excavation dewatering may be necessary. Contractor shall provide any and all tools, equipment and labor necessary for excavation dewatering no matter what the source. Dewatering shall be continuous until all site utilities are installed and backfilled.

1.08 EXISTING SITE CONDITIONS

A. Contractor shall acquaint himself with all site conditions. If unknown active utilities are encountered during work, notify Architect promptly for instructions. Failure to notify will make Contractor liable for damage to these utilities arising from Contractor's operations subsequent to discovery of such unknown active utilities.

1.09 ON SITE UTILITY VERIFICATION AND REPAIR PROCEDURES

- A. Ground-breaking requirements:
 - 1. All underground work performed by a Contractor must be authorized by the District's Construction Manager or the Low Voltage Consultant prior to start of construction.
 - 2. The Contractor is to obtain and keep the original School's construction utility site plans on site during all excavation operations. Contractor can contact the District's Construction Manager, Facilities Manager, or the Low Voltage Consultant to procure the drawings.
- B. Underground Utility Locating:
 - 1. The contractor shall hire an Underground Utility Locating Service to locate existing underground utility pathways in areas affected by the scope of work for excavation.
 - 2. Contractor must use an underground utility locator service with a minimum of 3 years' experience. The equipment operator must have demonstrated experience.
 - 3. The Underground Utility Locator Service must have the use of equipment with the ability to locate by means of inductive clamping, induction, inductive metal detection, conductive coupling, or TransOnde (Radio detection) to generate signals, passive locating (free scoping) for "hot" electric, and metal detector.
 - 4. The Underground Utility Locator Service must be able to locate existing utilities at a depth of at least 72".
 - 5. The Underground Utility Locator Service must be able to locate but are not limited to locating the following types of utility pathways:
 - a) All conduit pathways containing 110 volt or greater 50-60Hz electrical wire.
 - b) All conduit pathways containing an active cable TV system.
 - c) All conduit pathways containing wire or conductor in which a signal can be attached and

generated without damaging or triggering the existing systems.

- d) All empty conduit pathways or pipe in which a signal probe or sonde (miniature transmitter) can be inserted.
- e) All conduit pathways containing non-conductive cables or wires in which a signal probe or sonde (miniature transmitter) can be inserted.
- f) All plastic and other nonconductive water lines in which a TransOnde Radio detection) or other "transmitter" can be applied to create a low frequency pressure waive (signal) without damaging or triggering the existing systems.
- g) All copper or steel waterlines and plastic or steel gas lines

G. The site and adjacent influenced areas shall be watered as required to suppress dust nuisance. Dust control measures shall be in accordance with the local jurisdiction.

1.11 SEASONAL LIMITS

- A. No fill material shall be placed, spread or rolled during unfavorable weather conditions. When work is interrupted by rains, fill operations shall not be resumed until field tests indicate that moisture content and density of fill are satisfactory.
- B. Excessively wet fill material shall be bladed and aerated per section 3.08, B.

1.12 TESTING

- A. General: Refer to Section 01 45 00 Quality Requirements.
- B. Geotechnical Engineer: Owner is retaining a Geotechnical Engineer to determine compliance of fill with Specifications, and to direct adjustments in fill operations. Costs of Geotechnical Engineer will be borne by Owner; except those costs incurred for re-tests or re-inspection will be paid by Owner and back charged to Contractor.
 - 1. If Contractor elects to process or mine onsite materials for use as Suitable Fill, Aggregate Sub Base, Aggregate Base, Rock, Crushed Rock or sand the cost of all testing of this material shall be paid for by the Contractor.
 - 2. Testing of import fill for compliance with Department of Toxic Substance Control (DTSC) shall be paid for by the Contractor.

1.13 ARCHEOLOGICAL AND CULTURAL RESOURCES

A. If archeological or cultural resources are discovered during the Work, the Contractor must cease all Atentic restriction (g)0J33848

EARTHWORK 31 00 00 - 6

EARTHWORK 31 00 00 - 7

EARTHWORK 31 00 00 - 8

- B. Do all cutting necessary to bring finish grade to elevations shown on Drawings.
- C. When excavation through roots is necessary, cut roots by hand.
- D. Carefully excavate around existing utilities to avoid unnecessary damage. The contractor shall anticipTd [(U)10..

B. Selected fill material shall be moisture-conditioned to specified moisture content. Selected fill material shall be unfrozen. When moisture content of fill material is below that specified, add water until proper moisture content is achieved. When moisture content is above that specified, aerate by

EARTHWORK 31 00 00 - 11 PART 1 – GENERAL

PART 3 – EXECUTION

PART 1 - GENERAL
SECTION 32 16 00

SITE CONCRETE

may be waived in accordance with Section 1910A.2 when approved by the Structural Engineer and DSA.

1.08 ADEQUACY AND INSPECTION

- A. Design, erect, support, brace and maintain formwork and shoring to safely support all vertical and lateral loads that might be applied until such loads can be carried by concrete.
- B. Notify Inspector, Architect and DSA at least 48 hours prior to placing of concrete.

1.09 **PROTECTION**

A. Finish surfaces shall be protected at all times from concrete pour. Inspect forming against such work and establish tight leak-proof seal before concrete is poured. Finish work damaged, defaced or vandalized during the course of construction shall be replaced by contractor at contractor expense.

1.10 FIELD MEASUREMENTS

A. Make and be responsible for all field dimensions necessary for proper fitting, slopes and completion of work. Report discrepancies to Architect before proceeding.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Cement: Portland cement, ASTM C150, Type II, per ACI 318-14 Section 26.4.
- B. Concrete Aggregates: Normal weight aggregates shall conform to ASTM C33, except as modified by this section. Combined grading shall meet limits of ASTM C33. Lightweight aggregate shall conform to ASTM C330, suitably processed, washed and screened, and shall consist of durable particles without adherent coatings.
- C. Water: Clean and free from deleterious amounts of acids, alkalis, scale, or organic materials and per ACI 318-14 Section 26.4.1.3.1.
- D. Fly Ash: Western Fly Ash, conforming to ASTM C618 for Class N or Class F materials (Class C is not permitted). Not more than 15% (by mass) may be substituted for portland cement.
- E. Water Reducing Admixture: Admixture to improve placing, reduce water cement ratio, and ultimate shrinkage may be used. Provide WRDA 64 by Grace Construction Products or approved equal. Admixture shall conform to ASTM C494 and ACI 318-14 Section 26.4.1.4.19(a). Such admixture must receive prior approval by the Architect, Structural Engineer, and the Testing Lab, and shall be included in original design mix.
- F. Air-entraining Admixture: Daravair 1000 by Grace Construction Products or approved equal. Admixture must conform to ASTM C260 and ACI 318-14, section 26.4.1.4.
- G. Surface Retarder (for exposed aggregate finishes): Rugasol-S by Sika Corporation or approved equal.

an approved equal.

T. Adhesive Anchoring (Epoxy): Hilty HIT-HY 200 Safe Set, or approved equal.

2.02 CONCRETE DESIGN AND CLASS

A. Class "B": Concrete shall have 1" max. size aggregat

nor the maximum slump is exceeded. In no case shall more than 10 gallons of water shall be added to a full 9 yard load, or 1 gal. per yard on remaining concrete within the drum providing load tag indicates at time of mixing at plant will allow for additional water.

2.04 MATERIALS TESTING

- A. Materials testing of concrete and continuous batch plant inspection may be waived in accordance CBC Sections 1704A.4.4 when approved by Structural Engineer and DSA.
- B. Testing of concrete shall be performed per article 3.12 of this specification.

2.05 EQUIPMENT

A. Handling and mixing of concrete: Project Inspector may order removal of any equipment which in his opinion is insufficient or in any way unsuitable.

PART 3 - EXECUTION

3.01 APPROVAL OF FORMS AND REINFORCEMENTS

- A. Forms and reinforcements are subject to approval by the Project Inspector, and notice of readiness to place first pour shall be given to DSA, Architect and Structural Engineer 48 hours prior to placement of concrete. Before placing concrete, clean tools, equipment and remove all debris from areas to receive concrete. Clean all reinforcing and other embedded items off all coatings oil, and mud that may impair bond with concrete.
- B. All reinforcing steel shall be adequately supported by approved devices on centers close enough to prevent any sagging.
- C. All reinforcing bar lap splices shall be staggered a minimum of 5 ft.

no additional cost to the Owner.

C. Sub-Grade in vehicular concrete paved areas: Subgrade shall be clean, shaped and compact to hard surface free from elevations or depressions exceeding 0.05' in 10' from true plan. Compact per Section 31 00 00. Compaction and moisture content shall be verified immediately prior to placement of concrete. Proof roll subbase in presence of geotechnical engineer prior to placement of aggregate base.

3.03 CLEANING

- A. Reinforcement and all other embedded items at time of placing concrete to be free of rust, dirt oil or any other coatings that would impair bond to concrete.
- B. Remove all wood chips, sawdust, dirt, loose concrete and other debris just before concrete is to be poured. Use compressed air for inaccessible areas. Remove all standing water from excavations.

3.04 FORMING

- A. Form material shall be straight, true, sound and able to withstand deformation due to loading and effects of moist curing. Materials which have warped or delaminated, or require more than minor patching of contact surfaces, shall not be reused.
- B. Build forms to shapes, lines, grades and dimensions indicated. Construct form work to maintain tolerances required by ACI 301. Forms shall be substantial, tight to prevent leakage of concrete, and properly braced and tied together to maintain position and shape. Butt joints tightly and locate on solid backing. Chamfer corners where indicated. Form bevels, grooves and recesses to neat, straight lines. Construct forms for easy removal without hammering, wedging or prying against concrete.
- C. Space clamps, ties, hangers and other form accessories so that working capacities are not exceeded by loads imposed from concrete or concreting operations.
- D. Build openings into vertical forms at regular intervals if necessary to facilitate concrete placement, and at bottoms of forms to permit cleaning and inspection.
- E. Build in securely braced temporary bulkheads, keyed as required, at planned locations of construction joints.
- F. Slope tie-wires downward to outside of wall.
- G. Brace, anchor and support all cast-in items to prevent displacement or distortion.
- H. During and immediately after concrete placing, tighten forms, posts and shores. Readjust to maintain grades, levels and camber.

concrete section. Recess for backer rod and sealant where required. Expansion joints shall not exceed ¼ inch depth measured from finish surface to top of felt or sealant, and ½ inch width.

- 2. Curbs, Valley Gutter, and Curb & Gutter: Install expansion joints at 60' on center, except when placing adjacent to concrete walks, the expansion joints shall align with the expansion joints shown for the concrete walks. Expansion joint material shall be full depth of concrete section. Recess for backer rod and sealant will be required.
- 3. Isolation Joints: 3/8" felt between walls and exterior slabs or walks so that paved areas are isolated from all vertical features, unless specifically noted otherwise on plans.
- 4. Exterior Concrete Paving: Install expansion joints at 20' on center maximum, both directions, unless shown otherwise on plans.
- 5. Ramps; whether shown or not all ramps shall have control joints and expansion joints.
- a. Control joints on ramps shall be aligned and be placed in between with the vertical posts for the handrails. The curbs, if required shall have control joints that align with the handrail posts.
- b. Expansion joints shall be placed at the upper, intermediate, and bottom landings.

3.05 FORM COATING

- A. Before placement of reinforcing steel, coat faces of all forms to prevent absorption of moisture from concrete and to facilitate removal of forms. Apply specified material in conformance with manufacturer's written directions.
- B. Before re-using form material, inspect, clean thoroughly and recoat.
- C. Seal all cut edges.

3.06 INSTALLATION

- A. General: Reinforcement shall be accurately placed at locations indicated on the drawings within required tolerances and providing required clearances. Reinforcement shall be secured prior to placement of concrete such that tolerances and clearances are maintained. Coverage shall be in accordance with Section 1907A.7 of the CBC. Keep a person on the job to maintain position of reinforcing as concrete is placed. Reinforcement must be in place before concreting is begun. Install dowels as shown on drawings. Give notice whenever pipes, conduits, sleeves, and other construction interferes with placement; obtain method of procedure to resolve interferences. All expansion and construction joints in concrete shall have dowels of size and spacing as shown, or as approved by Architect.
- B. Placing Tolerances:
 - 1. Per ACI 301 or CRSI/WCRSI Recommended Practice for Placing Reinforcing Bars, unless otherwise shown.
 - 2. Clear distance between parallel bars in a layer shall be no less than 1", the maximum bar diameter not 1 ½ times the maximum size of coarse aggregate.
- C. Splices:

- 1. General: Unless otherwise shown on drawings, splice top reinforcing at midspan between supports, splice bottom reinforcing at supports and stagger splices at adjacent splices 5 foot minimum. Bar laps shall be wired together. Reinforcing steel laps shall be as follows:
 - a. Lap splices in concrete: Lap splice lengths shall not be

the maximum specified tolerances shall be made level by the Contractor at no additional expense to the Owner.

- 2. Concrete vibrator shall be used to assist concrete placement. Contractor shall have spare concrete vibrator on site during concrete placement.
- I. Placing in hot weather: Comply with ACI 305R-10. Concrete shall not exceed 85 degrees F at time of placement. Concrete shall be delivered, placed and finished in a sufficiently short period of time to avoid surface dry checking. Concrete shall be kept wet continuously after tempering until implementation of curing compound procedure in accordance with this specification.
- J. Placing in cold weather: Comply with ACI 306R-16. Protect from frost or freezing. No antifreeze admixtures are permitted. When deposited concrete during freezing or near-freezing weather, mix shall have temperature of at least 50 degrees F but not more than 90 degrees F. Concrete shall be maintained at temperature of at least 50 degrees F for not less than 72 hours after placing or until it has thoroughly hardened. Provide necessary thermal coverings for any flat work exposed to freezing temperatures.
- K. Horizontal construction joint: Keep exposed concrete face of construction joints continuously moist from time of initial set until placing of concrete; thoroughly clean contact surface by chipping entire surface not earlier than 5 days after initial pour to expo

- C. As directed by Architect, cut out and replace defective concrete. All defective concrete shall be removed from the site. No patching is to be done until surfaces have been examined by Architect and permission to begin patching has been provided.
- D. Permission to patch any area shall not be considered waiver of right, by the Owner, to require removal of defective work, if patching does not, in opinion of Architect, satisfactorily restore quality and appearance of surface.
- E. Defective concrete is:
 - 1. Concrete that does not match the approved mix design for the given installation type.
 - 2. Concrete not meeting specified 28-day strength.
 - 3. Concrete which contains rock pockets, voids, spalls, transverse cracks, exposed reinforcing, or other such defects which adversely affect strength, durability or appearance.
 - 4. Concrete which is incorrectly form,

SECTION 32 31 13

CHAIN LINK FENCES AND GATES

PART 1 - GENERAL

1.01 SUMMARY

- A. SECTION INCLUDES
 - 1. Fence framework, fabric, and accessories.
 - 2. Excavation for post bases; concrete foundation for posts.
 - 3. Manual gates and related hardware.

1.04 QUALITY ASSURANCE

A. Manufacturer: Company specializing in manufacturing the products specified in this section with

H. Concrete: ASTM C94; Portland Cement, 2,500 p.s.i. strength at 28 days, 3 inch slump; one inch

SECTION 32 31 19

DECORATIVE METAL FENCES AND GATES

PART 1 - GENERAL

1.01 SUMMARY

- A. SECTION INCLUDES:
 - 1. Ornamental picket fencing, gates and accessories.
- **B. RELATED SECTIONS:**
 - 1. The General Conditions, Supplementary Conditions and Division 1 are fully applicable to this Section, as if repeated herein.
 - 2. Section 08 71 00: Door Hardware (except hinges which are specified herein).
 - 3. Section 32 13 00: Portland Cement Concrete Paving.

1.03 SUMBITTALS

A. Shop Drawings: Layout of all fences and gates with dimensions, details and finishes of component

Phone (888) MH-Fence, (888) 643-3623

- 2. Ameristar, Tulsa, OK Phone (888) 333-3422
- 3. Merchant Metals Phone (770) 741-0300

- H. Where touch up paint is necessary, paint shall match powder coated finish. Unacceptable finishes will require re-powder coating.
- I. Cutting of manufacturer's brackets will not be accepted.

3.03 GATE INSTALLATION

A. Install gates plumb, level and secure for full opening without interference.